



Indicative only

Tree Work Schedule			
No.	Species	Works	Category
1	London plane	[Red to ground level and grind out stump]	A12

All tree work to be undertaken in accordance with British Standard BS 3998:2010 Tree work - Recommendations. All arising areas to be removed and the site is to be left as found. Care is to be taken of the ground around retained trees to make sure that it does not become compacted as a result of tree surgery operations. No equipment or vehicles such as timber lorries, tractors, excavators or cranes shall be parked or driven beneath the crowns of any retained trees, to prevent subsequent compaction and root death.

No. of individual trees to be removed			
U	A	B	D
0	1	0	0

No. of groups / hedges to be removed			
U	A	B	D
0.00	0.00	0.00	0.00

U = Partial removal of a group

**Note:** Tree to be removed due immediate requirement and future pressure to prune due to juxtaposition between the proposed built form and future tree growth.

The construction and placement of the proposed building would require significant pruning treatments to the extent of both crown shape disfigurement and large diameter branch removal causing wounds which are unlikely to be effectively compartmentalised and risk the onset of decay and/or disease.

The true root morphology on site will have been dictated on site by previous building foundations and is unlikely to be well represented by the notional RPA. However, the new foundations for the structure at the boundary of the site is likely to cause significant damage to the rooting area which primarily imparts structural stability.

The tree sits outside of the site boundary and permission to remove the tree must be sought from the landowner.



Unit 3, Well House Barns, Chester, CH4 0DH  
<https://arbtech.co.uk>, 01244 681170

Client: Sky Eagle Properties Ltd

Drawing: Arbicultural Impact Assessment

Based on: 621P05 B

Drawing No: Arbtech AIA 01

Date: Nov 2023 Scale: 1:50 @ A0 Drawn: DM

Key:			
Tree No. 1	Tree Category	Trunk	
RPA	Category	Trunk	
Existing Site	Proposed Site	Trees to be removed	

This drawing was produced in colour. A monochrome copy should be used for printing. The drawing was produced in colour. A monochrome copy should be used for printing.

